


**DILE MINI CONTACTOR RELAY**  
**010157**

  
Overview

  
Specifications

  
Resources

**How to buy**



# 010157

Eaton Moeller® series DILER Contactor relay, 24 V  
3 N/O, N/C = Normally closed: 1 NC, Screw terminal  
G(24VDC)

**How to buy**

Photo is representative

## GENERAL SPECIFICATIONS

General specifications >

**PRODUCT NAME** Eaton Moeller® series DILER Control Relay

**CATALOG NUMBER** 010157

Product specifications >

**MODEL CODE** DILER-31-G(24VDC)

**EAN** 4015080101574

**PRODUCT LENGTH/DEPTH** 54 mm

**PRODUCT HEIGHT** 58 mm

**PRODUCT WIDTH** 45 mm

**PRODUCT WEIGHT** 0.206 kg

UL 508  
UL  
CE

## CERTIFICATIONS

VDE 0660  
IEC/EN 60947-4-1  
CSA  
CSA-C22.2 No. 14-05  
CSA File No.: 012528  
EN 60947-5-1  
UL File No.: E29184  
IEC/EN 60947  
UL Category Control No.: NKCR  
CSA Class No.: 3211-03

## PRODUCT SPECIFICATIONS

<b>RATED OPERATIONAL CURRENT FOR SPECIFIED HEAT DISSIPATION (IN)</b>	6 A
<b>TERMINAL CAPACITY (FLEXIBLE WITH FERRULE)</b>	1 x (0.75 - 1.5) mm <sup>2</sup> 2 x (0.75 - 1.5) mm <sup>2</sup>
<b>10.11 SHORT-CIRCUIT RATING</b>	Is the panel builder's responsibility. The specifications must be observed.
<b>RATED CONTROL SUPPLY VOLTAGE (US) AT AC, 50 HZ - MIN</b>	0 V
<b>10.4 CLEARANCES AND CREEPAGE DISTANCES</b>	Meets the product standard's requirements.
<b>MOUNTING METHOD</b>	DIN-rail/screw
<b>OPERATING VOLTAGE AT DC - MAX</b>	220 VDC
<b>10.2.3.1 VERIFICATION OF THERMAL STABILITY OF ENCLOSURES</b>	Meets the product standard's requirements.
<b>FITTED WITH:</b>	Interlocked opposing contacts
<b>RATED CONTROL SUPPLY VOLTAGE (US) AT AC, 50 HZ - MAX</b>	0 V
<b>OPERATING VOLTAGE AT DC - MIN</b>	24 VDC
<b>AMBIENT OPERATING TEMPERATURE - MAX</b>	50 °C
<b>FEATURES</b>	Positive operating contacts to EN 60947-5-1 appendix auxiliary contact module
<b>POWER CONSUMPTION (SEALING) AT DC</b>	2.3 W
<b>VOLTAGE TOLERANCE</b>	Smoothed DC, three-phase bridge rectifiers or smoothed rectification
<b>AMBIENT OPERATING TEMPERATURE - MIN</b>	-25 °C
<b>10.6 INCORPORATION OF SWITCHING DEVICES AND COMPONENTS</b>	Does not apply, since the entire switchgear needs to
<b>10.2.6 MECHANICAL IMPACT</b>	Does not apply, since the entire switchgear needs to
<b>10.3 DEGREE OF PROTECTION OF ASSEMBLIES</b>	Does not apply, since the entire switchgear needs to

<b>APPLICATION</b>	Contactor relays
<b>RATED OPERATIONAL CURRENT (IE) AT AC-15, 380 V, 400 V, 415 V</b>	3 A
<b>OPERATING FREQUENCY</b>	9000 Operations/h
<b>VOLTAGE TYPE</b>	DC
<b>PRODUCT CATEGORY</b>	DILER Mini-contactors
<b>HEAT DISSIPATION CAPACITY PDISS</b>	0 W
<b>CONNECTION TYPE (AUXILIARY CIRCUIT)</b>	Screw connection
<b>SHORT-CIRCUIT PROTECTION RATING WITHOUT WELDING</b>	6 A gG/gL, 500 V, Max. Fuse, Contacts
<b>OPERATING VOLTAGE AT AC, 60 HZ - MAX</b>	500 V
<b>TERMINAL CAPACITY (SOLID/STRANDED AWG)</b>	1 x (18 - 14) 2 x (18 - 14) 18 - 14
<b>10.9.2 POWER-FREQUENCY ELECTRIC STRENGTH</b>	Is the panel builder's responsibility.
<b>DEGREE OF PROTECTION</b>	IP20
<b>OVERVOLTAGE CATEGORY</b>	III
<b>VOLTAGE TYPE OF OPERATING VOLTAGE</b>	AC/DC
<b>POLLUTION DEGREE</b>	3
<b>RATED IMPULSE WITHSTAND VOLTAGE (UIMP)</b>	6000 V AC
<b>OPERATING VOLTAGE AT AC, 60 HZ - MIN</b>	17 V
<b>TIGHTENING TORQUE</b>	1.2 Nm, Screw terminals
<b>10.2.2 CORROSION RESISTANCE</b>	Meets the product standard's requirements.
<b>10.2.4 RESISTANCE TO ULTRA-VIOLET (UV) RADIATION</b>	Meets the product standard's requirements.
<b>10.2.7 INSCRIPTIONS</b>	Meets the product standard's requirements.
<b>NUMBER OF CONTACTS (NORMALLY OPEN CONTACTS)</b>	3
<b>NUMBER OF AUXILIARY CONTACTS (NORMALLY OPEN CONTACTS)</b>	3
<b>SHOCK RESISTANCE</b>	8 g, N/C auxiliary contact, Basic unit with auxiliary Mechanical, according to IEC/EN 60068-2-27, Half ms 10 g, N/O auxiliary contact, Basic unit with auxilia Mechanical, according to IEC/EN 60068-2-27, Half ms
<b>SWITCHING TIME (DC OPERATED, MAKE CONTACTS, OPENING DELAY) - MIN</b>	15 ms
<b>AMBIENT OPERATING TEMPERATURE (ENCLOSED) -</b>	25 °C

<b>MIN</b>	20 V
<b>OPERATING VOLTAGE AT AC, 50 HZ - MAX</b>	500 V
<b>10.12 ELECTROMAGNETIC COMPATIBILITY</b>	Is the panel builder's responsibility. The specifications must be observed.
<b>10.2.5 LIFTING</b>	Does not apply, since the entire switchgear needs to be lifted.
<b>NUMBER OF AUXILIARY CONTACTS (NORMALLY CLOSED CONTACTS, DELAYED SWITCHING)</b>	0
<b>STRIPPING LENGTH (MAIN CABLE)</b>	8 mm
<b>AMBIENT OPERATING TEMPERATURE (ENCLOSED) - MAX</b>	40 °C
<b>RATED CONTROL SUPPLY VOLTAGE (US) AT DC - MIN</b>	24 V
<b>10.8 CONNECTIONS FOR EXTERNAL CONDUCTORS</b>	Is the panel builder's responsibility.
<b>SCREW SIZE</b>	M3.5, Terminal screw
<b>NUMBER OF AUXILIARY CONTACTS (NORMALLY OPEN CONTACTS, LEADING)</b>	0
<b>PROTECTION</b>	Finger and back-of-hand proof, Protection against dirt, actuated from front (EN 50274)
<b>CLIMATIC PROOFING</b>	Damp heat, constant, to IEC 60068-2-78 Damp heat, cyclic, to IEC 60068-2-30
<b>CODE NUMBER</b>	31E
<b>STATIC HEAT DISSIPATION, NON-CURRENT-DEPENDENT PVS</b>	2.3 W
<b>RATED OPERATIONAL CURRENT (IE) AT AC-15, 500 V</b>	1.5 A
<b>RATED CONTROL SUPPLY VOLTAGE (US) AT DC - MAX</b>	24 V
<b>10.9.3 IMPULSE WITHSTAND VOLTAGE</b>	Is the panel builder's responsibility.
<b>10.5 PROTECTION AGAINST ELECTRIC SHOCK</b>	Does not apply, since the entire switchgear needs to be lifted.
<b>SAFE ISOLATION</b>	300 V AC, Between coil and auxiliary contacts, According to IEC 60074-1 300 V AC, Between auxiliary contacts, According to IEC 60074-1
<b>OPERATING VOLTAGE AT AC, 50 HZ - MIN</b>	17 V
<b>MOUNTING POSITION</b>	As required (except vertical with terminals A1/A2 at the top)
<b>RATED OPERATIONAL CURRENT (IE) AT AC-15, 220 V, 230 V, 240 V</b>	6 A
<b>10.13 MECHANICAL FUNCTION</b>	The device meets the requirements, provided the instructions in the instruction leaflet (IL) is observed.
<b>10.9.4 TESTING OF ENCLOSURES MADE OF INSULATING MATERIAL</b>	Is the panel builder's responsibility.
<b>NUMBER OF CONTACTS (NORMALLY CLOSED CONTACTS)</b>	1

<b>HEAT DISSIPATION PER POLE, CURRENT-DEPENDENT PVID</b>	0.4 W
<b>ACTUATING VOLTAGE</b>	24 V DC
<b>SWITCHING TIME (DC OPERATED, MAKE CONTACTS, OPENING DELAY) - MAX</b>	25 ms
<b>SWITCHING CAPACITY (AUXILIARY CONTACTS, GENERAL USE)</b>	0.5 A, 250 V DC, (UL/CSA) 10 A, 600 V AC, (UL/CSA)
<b>SWITCHING TIME (DC OPERATED, MAKE CONTACTS, CLOSING DELAY) - MAX</b>	35 ms
<b>EQUIPMENT HEAT DISSIPATION, CURRENT-DEPENDENT PVID</b>	0 W
<b>RATED SWITCH CURRENT</b>	10 A
<b>RATED OPERATIONAL CURRENT (IE)</b>	1.5 A at 110 V, DC L/R ≤ 15 ms (with 3 contacts in parallel) 2.5 A at 60 V, DC L/R ≤ 15 ms (with 2 contacts in parallel) 0.5 A at 220 V, DC L/R ≤ 15 ms (with 3 contacts in parallel) 2.5 A at 24 V, DC L/R ≤ 15 ms (with 1 contact in parallel) 10 A
<b>PICK-UP VOLTAGE</b>	0.85 - 1.3 V DC x U <sub>c</sub> 0.7 - 1.3 V DC x U <sub>c</sub> (at 24 V: without auxiliary contact) ambient air temperature + 40 °C)
<b>TERMINAL CAPACITY (SOLID)</b>	1 x (0.75 - 2.5) mm <sup>2</sup> 2 x (0.75 - 2.5) mm <sup>2</sup>
<b>NUMBER OF AUXILIARY CONTACTS (NORMALLY CLOSED CONTACTS)</b>	1
<b>10.2.3.2 VERIFICATION OF RESISTANCE OF INSULATING MATERIALS TO NORMAL HEAT</b>	Meets the product standard's requirements.
<b>SWITCHING TIME (DC OPERATED, MAKE CONTACTS, CLOSING DELAY) - MIN</b>	26 ms
<b>10.2.3.3 RESIST. OF INSUL. MAT. TO ABNORMAL HEAT/FIRE BY INTERNAL ELECT. EFFECTS</b>	Meets the product standard's requirements.
<b>LIFESPAN, MECHANICAL</b>	20,000,000 Operations (DC operated)
<b>CONTROL CIRCUIT RELIABILITY</b>	< 2 λ, < 1 failure at 100,000,000 Operations (at U <sub>c</sub> = 17 V, I <sub>min</sub> = 5.4 mA)
<b>NUMBER OF AUXILIARY CONTACTS (CHANGE-OVER CONTACTS)</b>	0
<b>RATED OPERATIONAL VOLTAGE (UE) AT AC - MAX</b>	600 V
<b>RATED CONTROL SUPPLY VOLTAGE (US) AT AC, 60 HZ - MIN</b>	0 V
<b>10.7 INTERNAL ELECTRICAL CIRCUITS AND CONNECTIONS</b>	Is the panel builder's responsibility.
<b>SWITCHING TIME (DC OPERATED, N/O, WITH AUXILIARY CONTACT MODULE, CLOSING DELAY)</b>	70 ms

<b>POWER CONSUMPTION (PICK-UP) AT DC</b>	2.3 W
<b>10.10 TEMPERATURE RISE</b>	The panel builder is responsible for the temperature Eaton will provide heat dissipation data for the device
<b>CONVENTIONAL THERMAL CURRENT I<sub>TH</sub> AT 50°C (3-POLE, OPEN)</b>	10 A
<b>SCREWDRIVER SIZE</b>	2, Terminal screw, Pozidriv screwdriver 0.8 x 5.5/1 x 6 mm, Terminal screw, Standard screw
<b>DUTY FACTOR</b>	100 %
<b>RATED CONTROL SUPPLY VOLTAGE (US) AT AC, 60 HZ - MAX</b>	0 V
<b>SHORT-CIRCUIT PROTECTION RATING</b>	10 A fast, 500V, Maximum fuse, Short-circuit rating Contacts
<b>SWITCHING CAPACITY (AUXILIARY CONTACTS, PILOT DUTY)</b>	A600, AC operated (UL/CSA) P300, DC operated (UL/CSA)
<b>RATED INSULATION VOLTAGE (UI)</b>	690 V

Catalogs

---

Characteristic curve

---

Declarations of conformity

---

Drawings

---

eCAD model

---

Installation instructions

---

mCAD model

---

System overview

---

Wiring diagrams

---



Eaton is an intelligent power management company dedicated to improving the quality of life and protecting the environment for people everywhere. We are guided by our commitment to do business right, to operate sustainably and to help our customers manage power — today and well into the future. By capitalizing on the global growth trends of electrification and digitalization, we're accelerating the planet's transition to renewable energy and helping to solve the world's most urgent power management challenges.